


In-Vessel Neutron Calibrations Planning, Progress, Constraints

Silvia di Sarra, Bruno Coriton, Vitaly Krasilnikov, Thierry
Martin and the Team

Introduction

- The purpose of the In-Vessel Neutron Calibration is to calibrate the Neutron Diagnostics in order to obtain accurate measurements of:
 - Neutron fluence
 - Fusion Power
 - Fusion Power Density
 - Neutron and Alpha source Profile
 - Neutron Yield
- Important: Fusion Power and Tritium accountancy
- How:
 - A neutron source is placed in the VV and irradiates the neutron diagnostics with known neutron fluxes, at predetermined positions/times, with energy distributions as close as possible to the plasma emission
 - ITER Machine neutronic models validation
- The calibration measured data and the validated model allow to **correlate detectors count rates to the measured parameters**



IVNC 1st Campaign Staging



IVNC Neutron Generator and control unit

(NG-24 by VNIIA)

IDM UID: XXXXXX


Page 2

Introduction

- IVNC Campaigns need to be repeated periodically for:
 - Neutronic models progressive improvement
 - Compensate for machine configuration changes
 - Compensate for long term detectors drifts and wear out effect in the machine
- 1st Campaign:
 - 3 Calibrated Diagnostics: NFM in EP#1, NAS in UP#18 and DNFM
 - Few irradiation points
 - First correction of the models: methodology consolidation
- 2nd and 3rd Campaigns:
 - Calibrated diagnostics and irradiation points maximization
 - Progressive improvement of the models
 - Machine configuration toward completion
- Following Campaigns
 - To compensate machine wear out and detectors drift

IVNC Schedule

IVNCs shall be performed periodically




General planning


Neutron Diagnostics shall be well calibrated especially for DT operation

- ITER is a DT machine
- DD operation
 - Limited
 - Reaches low power
 - No significant Tritium production
- The baseline foresees calibration campaigns focused on DD generators
- Moving toward a strategy mainly focused on DT generators

Campaign	Phase	NG Type - Baseline	NG Type - Proposal
I	Pre-PFPO-1	DD	DD & DT
II	Pre-PFPO-2	DD	DT
III	Pre-FPO	DT	DT
Following	During Operation	DT	DT



Calibrated Diagnostics Location



- Ⓝ Neutron Flux Monitors
- ⓓ Divertor Neutron Flux Monitors
- Ⓜ MicroFission Chambers
- Ⓐ Neutron Activation System
- Ⓡ Radial Neutron Camera
- Ⓥ Vertical Neutron Camera

Calibrated Diagnostics

The number of directly calibrated detectors shall be maximized

- Calibration sources limited source strength allow direct calibration of only part of the Neutron Detectors
- Through the IVNC Campaigns, we are targeting to directly calibrate at least the most sensitive detector in the location specified below:
 - NFM#1 (1/4)
 - One MFC location (1/2)
 - NAS in UP#18, EP#17, VV surface in Sector 9 (4/8)
 - Two DNFM locations (2/3)
- Cross-Calibrations with standard plasma discharges will be performed for the other diagnostics

Can we calibrate the Cameras in-situ?

Neutron Source Choice

The neutron source used during IVNC shall be as close as possible to the fusion plasma source.


- Former candidates:
 - DD Campaigns: ^{252}Cf (2.5 MeV neutrons)
 - DT Campaigns: Neutron Generators (14 MeV neutrons)
- **Current choice: Neutron Generators only (2.5 MeV and 14 MeV)**
- Californium discarded because:
 - Difficult recovery
 - High activity
 - Difficult shielding
 - Highly regulated

Required Machine Condition


Calibration conditions shall be as close as possible to operation conditions

- As close as possible to Operation conditions
 - Blanket modules in place
 - Divertor Cassettes in place
 - Port Plugs in place
 - Cooling water in IBED loops (room temperature and 1 bar)
- Set of already commissioned systems:
 - Calibrated Diagnostics
 - IBED cooling loops
 - 55.BV components


Campaign 1






Campaign 1 – Support Structure & Railway




- A Support Structure is installed on the Fixing System which is pre-installed in the Blankets by MA
- Guiding Rails are used by the Tool to move toroidally.
- The complete angle of this Railway is 210°



Campaign 1 – Some NG Positions



Campaign 1 - Target Diagnostics



- (N) Neutron Flux Monitors
- (D) Divertor Neutron Flux Monitors
- (M) MicroFission Chambers
- (A) Neutron Activation System
- (R) Radial Neutron Camera
- (V) Vertical Neutron Camera


● Targeted Diagnostics

1st Campaign Staging coverage

- **Neutron Flux Monitor (P9 to P13):**


Campaign 2, 3 and following

Campaign 2, 3 and following - Target Diagnostics



- (N) Neutron Flux Monitors
- (D) Divertor Neutron Flux Monitors
- (M) MicroFission Chambers
- (A) Neutron Activation System
- (R) Radial Neutron Camera
- (V) Vertical Neutron Camera
- Calibration Primary Target
- Secondary for Calibration


Campaign 2, 3 and following - Irradiation Plan



- Toroidal scan (13 points)

- 13 irradiation positions 20° apart from each other
- Magnetic axes level
- Covering 260° (Port 13 to Port 8)


Campaign 2, 3 and following - Irradiation Plan



- Neutron Flux Monitors (6 points):


- Radial and vertical scan for EP#1
- One point for NFM#7

Campaign 2, 3 and following - Irradiation Plan




- Divertor NFM (6 points)
 - 2/3 DNFM locations
 - Toroidal scan close to the detectors (3 points/location)

Campaign 2, 3 and following - Irradiation Plan



- Neutron Activation System (6 points)
 - 4/8 NAS Locations
 - One irradiation position per irradiation end

Campaign 2, 3 and following - Irradiation Plan




- Micro Fission Chambers (6 points)

- ½ MFC locations

- 3 toroidal positions for the upper

Campaign 2, 3 and following - Irradiation Plan Summary



- **37 Irradiation positions**
- **Toroidal scan (13 points)**
 - 13 irradiation positions 20° apart from each other
 - Magnetic axes level
 - Covering 260° (Port 13 to Port 8)
- **Neutron Flux Monitor (6 points):**
 - Radial and vertical scan for EP#1
 - One point for NFM#7
- **Divertor NFM (6 points)**
 - 2 locations
 - Toroidal scan close to the detectors
- **Neutron Activation System (6 points)**
 - One irradiation position per irradiation end
- **Micro Fission Chambers (6 points)**
 - 3 toroidal positions for the upper

Conclusion

- IVNC Campaigns will be crucial to achieve target accuracies and validate neutronic models
- Neutron Generators will be used to irradiate Neutron Diagnostics
- A dedicated tool (before PFPO-1) and a RH tool will be used to position the NGs in several VV locations
- Calibration Campaigns are time consuming and require specific ITER Machine configuration. Their placement in the overall schedule shall be very carefully planned



Thank you

Back-up



Why IBED hot water discarded

- Early integrated commissioning start (with machine in non-complete configuration)
- Double TCWS commissioning (without and with 3 DCs installed)
- Double TCWS valves calibration (2 weeks procedure)
- NG and electronics cooling difficult
- All components, including RH tool compatible with high temperature
- Long times required to fill up + heat up circuits → then cool down and drain

Campaign 1 – Complete view of the Tool and Its environment



Campaign 1 – Neutron Generator Deployment Tool



Performances:

Toroidal: Speed max 250 mm/s,

rotation axis = Tokamak Axis,

Power 0,25 Kw

Radial : Speed Max 150 mm/s,

stroke 1900 mm, Power 0,12 Kw

Vertical: Speed Max 375 mm/s,

stroke 6000 mm, Power 3 Kw

Generator Horizontal Rotation :

Angular Speed Max 6°/s, Stroke -

90° +20°, Power 0,55Kw

Generator Vertical Rotation:

Stroke +/- 45°, Electrical Jack

Force : 1200N


Campaign 1 - Planning

Context:

- End of Assembly Phase II, Long Term Maintenance
- Before the start of PFPO-1 Phase
- DCs installation – all installed except for the ones in front of LP14

Calibration sequence:

1. 55.BV components assembly (Access: LP14) → 3 days
 2. Commissioning activities + IBED Circuits filling → 1 day
 3. Irradiation → TBD
 4. Decay time + IBED draining → TBD
 5. 55.BV components disassembly → 3 days
- The VV will be a Be environment in this phase



Campaign 1 – Constraints and Challenges

Main challenge: schedule

- Required partial commissioning activity of TCWS (3 DCs are not installed)
- Assembly of 55.BV components in Be environment
- Activation after irradiation
- Careful placing in ITER Assembly and Commissioning Plan

Campaign 2, 3 and following - Planning

Context:

- Long Term Maintenance – Assembly Phase III, before PFPO-2
- Long Term Maintenance – Assembly Phase IV, before FPO
- Between Fusion Operation Campaigns

Calibration sequence:

1. RH Port(s) removal → 1 month
2. RH Tool Assembly + IBED loops filling → <1 week
3. Irradiation → weeks (TBD)
4. RH Port re-insertion & re-commissioning + IBED drain → 1.5 month

2.5 months required to remove, re-insert and re-commission RH port!

This activity can in principle be performed in parallel with others

Campaign 2, 3 – Constraints and Challenges

- These calibrations will be performed in high ionizing radiation fields
 - All components shall be rad-hard
- Schedule:
 - Despite the use of an agile RH Tool, these campaigns will be extremely expensive in terms of time